


MUNICIPAL CORPORATION BHILAI (C.G.)


NIT


कार्य का नाम :- वार्ड-06 प्रियदर्शनी परिसर पश्चिम में सीमेंटीकरण मार्ग निर्माण कार्य।

Pwd Road Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300.	472.50	Cum
2	Wet Mix Macadam (Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density as per clause 406.)	315.00	Cum
3	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads) P.C.C. M-10	46.90	Cum
4	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads) P.C.C. M-30	315.00	Cum


Executive Engineer
Municipal Corporation
Bhilai (C.G)


Asstt. Engineer
Municipal Corporation
Bhilai (C.G)


Sub. Engineer
Municipal Corporatio
Bhilai (C.G)