

MUNICIPAL CORPORATION OF BHILAI

DETAILED ESTIMATE

कार्य का नाम- वार्ड क्र. 58 सड़क 33 में बोर खनन कार्य 01 नग

S.N.	PARTICULARS OF ITEMS	Quantity	UOM
1	Carrying out the resistivity survey by VES method using Schlumberger configuration for locating the proper spot for drilling of tube well within the selected habitation, including photography, interpretation of resistivity data and submission of report in the desired format along with resistivity readings, necessary graph and photographs. (only successful point is payable)	1	Point
2	Boring/drilling bore well perfectly vertical for the specified depth suitable to receive required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and submitting strata chart/bore log, including hire & running charges of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer-in-charge upto 90 metre depth below ground level.		
	All types of soil 150 mm nominal dia	25	Metre
	Rocky strata including Boulders 150 mm nominal dia	45.00	Metre
3	Boring/drilling bore well perfectly vertical for the specified depth suitable to receive required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and submitting strata chart/bore log, including hire & running charges of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer-in-charge beyond 90 metre & upto 150 metre depth below ground level. Rocky strata including Boulders 150 mm nominal dia	15	Metre
4	Supplying, assembling, lowering and fixing in vertical position in bore well, ISI marked G.I. casing pipe (Plain) medium class in 4 to 7 meters length one end fitted with socket as per IS: 1239 (Part-1&Part-2) 1992 with IVth revision (Up-to-date amendments), of reputed & approved make, including required hire & labour charges, fittings & accessories, all complete, for all depths, as per direction of Engineer- in-charge. 150 mm nominal dia	26	Metre
5	Development of tube well in accordance with IS : 2800 (part I) and IS: 11189, to establish maximum rate of usable water yield without sand content (beyond permissible limit), with required capacity air compressor, running the compressor for ----- hire & labour charges of air compressor, tools & accessories etc., all as per requirement and direction of Eng.-in-charge.	4	Hrs
6	Providing and fixing suitable size threaded mild steel cap or spot welded plate to the top of bore well housing/ casing pipe, removable as per requirement, all complete for bore well of: 150 mm nominal dia	1	Each
7	Electrical SOR 01.06.2020 Supplying, installation, testing and commissioning of submersible pump set for water supply system with submersible motor directly coupled to multi-stage submersible pump of specified discharge capacity, head, delivery size in existing bore well including 2 sets of suitable size holding clamps made out of 50 mm X 6 mm MS flat, connection with suitable submersible cable of standard length etc. as per specification and IS: 694 (2010). 1.0 HP. three phase	1	Each
8	Supply, installation, testing and commissioning of 5-7.5 HP 3 phase submersible motor starter cum control wall/ floor mounted type made out of not less than 1.6 mm thick MS sheet and comprising of following panel mounting switchgears there in including connection inter-connection etc. as per specification. a) Phase indicating lamps with fuses and toggle switches 1 set b) 5/7.5 HP 3 phase DOL starter with over load and no volt relay 1 No c) 32 A "C" curve TPMCB 1 No d) Voltmeter 0-500 V with selector switch 1 set e) Ammeter 0-10 A with CT's and selector switch 1 set.	1	Each

9	Providing following size ISI marked FR PVC insulated , PVC sheathed, 3 core submersible copper conductor wire and IS: 694 (2010) 2.5 sq. mm	50	Metre
10	Supplying and fixing of following sizes 'B' class G I pipe with all necessary Tee's, bends, sockets in the suction/ delivery line including cutting and threading etc. as per specification. 25 mm dia.	25	Metre

Asstt. Engineer
Municipal Corporation
Bhilai(C.G.)

[Signature]
Sub. Engineer
Municipal Corporation
Bhilai(C.G.)