


MUNICIPAL CORPORATION BHILAI (C.G.)

NIT


कार्य का नाम :- वार्ड-18 कान्ट्रेक्टर कॉलोनी अजय मुर्गी फार्म, सरदार मोहल्ला, तारा लाल चंद्रवंशी से आनंद साहू घर तथा तिरंग चौक के पास पावर पंप के माध्यम से पीने योग्य पानी आपूर्ति हेतु पाईप लाईन का संघारण कार्य।

AS PER PWD BUILDING S.O.R 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Demolishing cement concrete including disposal of material within 50 metre lead.		
	1:3:6 or richer mix	32.40	cum
2	Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete:		
	15 mm dia. nominal bore	60.00	meter
	25 mm dia. nominal bore	100.00	meter
	50 mm dia. nominal bore	250.00	meter
3	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality:		
	Bib cock (250 grams)	12.00	each
4	Providing and fixing brass/ gun metal gate valve with C.I. wheel of approved quality (screwed end):		
	25 mm dia. nominal bore	4.00	each
	50 mm dia. nominal bore	4.00	each
5	Providing and fixing G.I. Union in G.I. pipe (New work) including cutting and threading the pipe and making long screws etc. complete:		
	20mm nominal bore	4.00	each
	50mm nominal bore	4.00	each
6	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.		
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	32.40	cum


Executive Engineer
Municipal Corporation
Bhilai (C.G)

Asstt. Engineer
Municipal Corporation
Bhilai (C.G)


Sub. Engineer
Municipal Corporation
Bhilai (C.G)