


MUNICIPAL CORPORATION BHILAI (C.G.)

NIT


कार्य का नाम :- वार्ड-09 गौतम नगर पुड़की पारा में पावर पंप के माध्यम से पीने योग्य पानी आपूर्ति हेतु पाईप लाईन का संचारण कार्य।

AS PER PWD BUILDING S.O.R 01.01.2015

| S.No. | Description and details of work | Qty. | Unit |
|-------|---|-------|-------|
| 1 | Demolishing cement concrete including disposal of material within 50 metre lead. | | |
| | 1:3:6 or richer mix | 12.15 | cum |
| 2 | Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete: | | |
| | 15 mm dia. nominal bore | 30.00 | meter |
| | 25 mm dia. nominal bore | 50.00 | meter |
| | 50 mm dia. nominal bore | 55.00 | meter |
| 3 | Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality: | | |
| | Bib cock (250 grams) | 6.00 | each |
| 4 | Providing and fixing brass/ gun metal gate valve with C.I. wheel of approved quality (screwed end): | | |
| | 25 mm dia. nominal bore | 2.00 | each |
| | 50 mm dia. nominal bore | 2.00 | each |
| 5 | Providing and fixing G.I. Union in G.I. pipe (New work) including cutting and threading the pipe and making long screws etc. complete: | | |
| | 20mm nominal bore | 2.00 | each |
| | 50mm nominal bore | 2.00 | each |
| 6 | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. | | |
| | 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). | 12.15 | cum |


Executive Engineer
Municipal Corporation
Bhilai (C.G)

Asstt. Engineer
Municipal Corporation
Bhilai (C.G)


Sub. Engineer
Municipal Corporation
Bhilai (C.G)