


MUNICIPAL CORPORATION BHILAI (C.G.)

NIT


कार्य का नाम :- वार्ड-06 संजय नगर लोहिया पेट्रोल पंप के पीछे बस्ती में पावर पंप के माध्यम से पीने योग्य पानी आपूर्ति हेतु पाईप लाईन का संधारण कार्य।

AS PER PWD BUILDING S.O.R 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Demolishing cement concrete including disposal of material within 50 metre lead.		
	1:3:6 or richer mix	11.70	cum
2	Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete:		
	15 mm dia. nominal bore	30.00	meter
	25 mm dia. nominal bore	50.00	meter
	50 mm dia. nominal bore	50.00	meter
3	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality:		
	Bib cock (250 grams)	6.00	each
4	Providing and fixing brass/ gun metal gate valve with C.I. wheel of approved quality (screwed end):		
	25 mm dia. nominal bore	2.00	each
	50 mm dia. nominal bore	2.00	each
5	Providing and fixing G.I. Union in G.I. pipe (New work) including cutting and threading the pipe and making long screws etc. complete:		
	20mm nominal bore	2.00	each
	50mm nominal bore	2.00	each
6	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.		
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	11.70	cum


Executive Engineer
Municipal Corporation
Bhilai (C.G)

Asstt. Engineer
Municipal Corporation
Bhilai (C.G)


Sub. Engineer
Municipal Corporation
Bhilai (C.G)