



NAGAR PALIK NIGAM BHILAI

NIT

वा. क्र.-23 घासीदास नगर में समता चौक एवं अम्बेडकर आवासा शीतला मंदिर के समीप सीमेंटीकरण मार्ग एवं नाली संघारण कार्य।

(As per P.W.D BUILDING/ROAD S.O.R. W.E.F. 01.01.2015)

S.N	PARTICULAR	QTY	UNIT
1	Excavation for all types and sizes of foundations, trenches and drains 0.....m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil		
		102.40	cum
2	Providing and laying nominal mix cement concrete with crushed form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).		
		12.80	cum
3	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using .. reinforcement and form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).		
		43.20	cum
4	Providing and placing in position reinforcement for R.C.C. work including .. drawings including cost of binding wire in foundation and plinth all complete:Thermo-Mechanically treated bars FE 415		
		1728.00	kg
5	Providing and fixing formwork including entering Foundations, footings, base of columns and plinth beam in any shape and size.		
		288.00	sqm
6	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.		
		16.00	cum
7	Carriage by mechanical transport for 5 km lead: Earth		
		92.16	cum
8	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads P.C.C. M-25		
		4.50	cum
 ASSISTANT ENGINEER NAGAR PALIK NIGAM, BHILAI		 SUB ENGINEER NAGAR PALIK NIGAM, BHILAI	