

2

MUNICIPAL CORPORATION OF BHILAI NIT


वार्ड 40 मंगल बाजार परिसर में प्रकाश व्यवस्था एवं अन्य विकास कार्य।

As Per PWD Building SOR 01.01.2015, Electrical SOR 01.06.2020 & NON SOR ITEM

SN	PARTICULERS OF ITEMS	QTY.	UNIT
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil	13.37	Cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40mm nominal size).	2.30	Cum
3	Providing and placing in position angle iron post and strut of required size including bottom to be split and bent at right angle in opposite direction for required length and drilling holes upto 10 mm dia as per requirement including priming coat with red oxide zinc chromate primer and placing the post/ strut in cement concrete block.	151.16	Kg
4	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	2.70	Cum
5	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	9.38	Cum
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars	469.20	Kg
7	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	261.84	Kg
8	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: (A) Foundations, footings, base of columns and plinth beam in any shape and size.	93.60	sqm
9	Providing and fixing in position chain linked steel wire fabric made of 4 mm dia G.I. wire of required width in mesh to concrete/ wooden/ angle iron posts including securing and screwing with 2mm dia G.I. wire, G.I. staples, G.I.U-nails or steel pins etc., complete. Aperture 50x50mm	45.00	sqm
10	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	21.60	Cum
11	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Pigment Coloured (rubber mould) precast interlock concrete blocks	42.00	sqm
12	Supplying and stacking of good earth at site including royalty, loading, unloading and carriage upto 5 km (earth measured in stacks will be reduced by 20% for payment).	12.00	Cum
13	Supplying and stacking at site well decayed cow dung manure from approved source, including loading, unloading and carriage upto 5 km (manure measured in stacks will be reduced by 8% for payment).	2.00	Cum
14	Spreading of sludge, dump manure or/and good earth in required thickness (Cost of sludge, dump manure or/ and good earth to be paid separately).	16.00	Cum
15	Providing and planting following herbs in garden including preparation of soil, base plantation, providing and spreading different fertilizers, soil and sand; Hedges like Alife, Dorenta, Tikoma etc	190	Each
16	Furn like Arica, China etc (3 year old)		
17	Hibiscus (Flower)/ Rose	10	Each
18	Carpet grass (well developed)	20	Each
		25.00	sqm

SN	PARTICULARS OF ITEMS	QTY.	UNIT
19	Grassing with 'Doob' grass including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn free from weeds and fit for mowing including supplying good earth if needed (the good earth shall be paid for separately). In rows 5 cm apart in either direction.	150.00	sqm
20	Supply Of Swaged steel tubular Pole as per IS 2713 with base plate of size 300 x 3000 x 6 mm welded at bottom ----- specified height including painting with one coat of red oxide zinc chromate primer. Designation 410 SP-26 height 9.00 metre	10	Each
21	Erection of steel tubular pole or rail pole in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size) foundation including excavation & refilling etc as required of 7 metre to 10 metre	10	Each
22	Supply & fixing water tight terminal box made of 1.6 mm.thick M S Sheet with detachable gland plate in bottom ----. 4 way connector & 1 No. SPMCB inside the box for cable connection fixed to pole with 2 Nos. Clamp made from 40 x 3 mm MS flat with 2 Nos. nut bolts dully painted with 2 coat red oxide paint & 2 coat aluminum paint complete as required 30 x 20 x 15 cms	10	Each
23	Supply & Making end termination with brass compression gland & aluminum lugs for following size armored aluminum conductor power cable of 1.1 KV grade as required 3 x 25 sq.mm	20	Each
24	Supply & fixing & cramping suitable size & all type aluminum ferule/lugs for following size 1.1 KV grade power cable core/lead pressed with high pressure cramping tool including connection to switch gear/MCCB etc as required 25 sq.mm.	40	Each
25	Supply & Fixing GI Pipe Along With wall or pole/support with 2 nos. MS clamp for protection of underground cable in approved manner including bolts & nuts or metal dash fasteners complete as required 40 mm dia	100.00	Meter
26	Painting new steel & other metallic surface with red oxide zinc chromate primer paint complete with supply of material labour etc including preparation of surface	63.00	Sqm
27	Supply and fixing following street light pole bracket on existing pole made out of 50 mm dia MS "B" class pipe welded to 300 mm long MS pole canopy of suitable dia at a angle of 102.50 including having MS triangular stiffner of size 150 X 50 X 5 mm thick, making arrangement for tightening the bracket with pole by providing suitable size heavy duty nuts and bolts in canopy, painting with one coat of approved steel primer etc. as required. Double Over Hang 1.50 metre Long	10	Each
28	Painting wood steel & other metallic surface with aluminum paint complete with material & labour including preparation of surface	63.00	Sqm
29	Providing & Laying Cast In situ Cement Concrete 1:3:6 graded stone aggregate 40 mm nominal size foundation including mixing with mechanical mixer compacting with vibrator finishing & currying etc complete but excluding formwork	2.54	Cum
30	Providing timber steel formwork for cement concrete work at all levels including removing of the same	8.48	Cum
31	Earthing with G.I. earth pipe 4.5 m long 40 mm dia including accessories & providing masonry enclosure with cover plate having locking arrangement watering pipe etc (But without charcoal & salt) as required	10	Set
32	Supplying and drawing following sizes of FR PVC insulated copper conductor, single core cable in the existing surface/ concealed, steel/ PVC conduit/ PVC casing capping as required. 3 x 2.50 sq.mm	450.00	Sqm
33	Providing and fixing porcelain re-wireble fuse carrier and base unit on wooden board including drilling holes on the board, screws, connections etc. as per specification. (Thimbeling shall be paid separately). 32 amps	30	Each
34	Supplying, installation, testing and commissioning of following 230/250 volts LED street light fitting with all accessories like driver, heat sink made of die cast aluminium with IP 66 protection and 5 KV surge protection on pole bracket complete as required and furnishing 2 Yrs Guarantee certificate from manufacturer. 90 watt	20	Each
35	Supplying and laying following sizes one number PVC insulated/ XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required. 2 x 16 sq. mm	500.00	Meter

SN	PARTICULERS OF ITEMS	QTY.	UNIT	Rate
36	NON SOR ITEM Providing & Planting well developed & healthy (5' and above) orna mental plants with digging holes soil filling & chemical & biological treatment like ficus cycas chhatim, bottle palm, supari palm, musanda & avenue palm, tree including 6th month maintenance till well established as directed Engineer In charge	20	Each	
37	NON SOR ITEM Providing & Planting well established flowering & orna mental plants or shrubs like nerium, bougainvillia, crotons, vidhya etc. with digging holes & chemical treatment including 6th month maintenance till well established as directed Engineer In charge	15	Each	
38	NON SOR ITEM Providing & Planting well developed succulent healthy orna mental plants with digging chemical treatment like thuja, cycas, lolina etc, including 6th month maintenance till well established as directed Engineer In charge	11	Each	


Executive Engineer
Municipal Corporation
Bhilai

Assistant Engineer
Municipal Corporation
Bhilai


Sub Engineer
Municipal Corporation
Bhilai