

5

MUNICIPAL CORPORATION BHILAI

NIT

कार्य का नाम :- सी.सी. रोड निर्माण, वेलकम गेट के सामने ब्लॉक 32, 33 के सामने
रोड वार्ड क्रमांक 53 विधानसभा भिलाई नगर ।

(As Per PWD Building & Road SOR works w.e.f 01/01/2015)

SN.	Details of Item	Qty.	Unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	39.25	Sqm
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	39.25	m ³
3	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads) P.C.C. M-10 @2789.00/Cum	39.38	m ³
4	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads) P.C.C. M-25	39.25	m ³

कार्यपालन अभियन्ता
नगर पालिक निगम, भिलाई

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाई