


MUNICIPAL CORPORATION BHILAI (C.G.)


NIT


कार्य का नाम :- जोन-01 अंतर्गत खम्हरिया एवं पिली मिट्टी चौक एस.एल.आर.एम. सेंटर में कम्पोस्ट पीट का संधारण कार्य।

Pwd Building Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal	5.00	Cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	5.00	Cum
3	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	25.77	Cum
4	Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	198.86	Sqm
5	Providing and making 15mm thick cement plaster of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	128.86	Sqm
6	25mm thick cement concrete flooring with 1:2:4 cement concrete (1 cement : 2 coarse sand : 4 graded stone aggregate 12.5 mm nominal size) finished with floating coat of neat cement.	195.60	Sqm
7	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	240.00	Kg
8	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.	45.00	Kg
9	Painting exterior surface with SMOOTH exterior paint of required shade as per manufacturer with cow dung processing to give protective and decorative finish including cleaning washing of surface etc. complete with On old work (One or more coats applied @ 0.83 ltr/ 10 sqm)	200.00	Sqm
10	Providing and applying 2mm thick ready mix exterior grade(manufactured with cow dung processing) on wall to make surface smooth and even	30.00	Sqm
11	6% for electrification/sanitary	9927.00	Rs


Executive Engineer
Municipal Corporation
Bhilai (C.G.)


Asstt. Engineer
Municipal Corporation
Bhilai (C.G.)


Sub. Engineer
Municipal Corporation
Bhilai (C.G.)