


MUNICIPAL CORPORATION BHILAI (C.G.)


NIT


कार्य का नाम :- जोन-01 नेहरू नगर ऑफिस का संधारण कार्य।

Pwd Building Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Removing of existing laid 60/80 mm thick precast interlocking concrete blocks.....	175.00	Sqm
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	11.23	Cum
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	4.50	Cum
4	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4 fine sand)	10.00	Sqm
5	Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	10.00	Sqm
6	Repairs to plaster in patches of area 2.5 sq. metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls with cement mortar 1:4 (1 cement : 4 fine sand) complete including disposal of rubbish to the dumping ground within 50metres lead : Thickness upto 15mm	6.00	Sqm
7	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm	20.00	Sqm
8	Painting exterior surface with SMOOTH exterior paint of required shade as per manufacturer with cow dung processing to give protective and decorative finish including cleaning washing of surface etc. complete with On old work (One or more coats applied @ 0.83 ltr/ 10 sqm)	560.00	Sqm
9	Providing & laying only for paver block 60mm/80mm thick precast interlocking concrete blocks of any and shape/ pattern. Over 50 mm thick.	175.00	Sqm
10	Distempering with washable distemper tmanufacturer with cow dung processing to give an even shade : On new work	400.00	Sqm
11	Painting on new work (two or more coats) to give an even shade with Premium synthetic enamel paint to give an even shade.	13.60	Sqm
12	Add Extra 8% For Electrification	11037.00	Rs
13	Add Extra 2% For Sanitary/ Water Supply	2759.00	Rs


Executive Engineer
Municipal Corporation
Bhilai (C.G)


Asstt. Engineer
Municipal Corporation
Bhilai (C.G)


Sub. Engineer
Municipal Corporatio
Bhilai (C.G)