

MUNICIPAL CORPORATION OF BHILAI

NIT

वार्ड-44, नेपाली मोहल्ला में स्थित शिव मंदिर समीप जीर्णोद्धार का कार्य।

(As Per PWD Building SOR 01.01.2015 & Electrical SOR 01.06.2020)

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	14.44	Cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	3.30	Cum
3	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	11.046	Cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete:Thermo-Mechanically treated bars	1104.60	Kg
5	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	3.46	Cum
6	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:		
(A)	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	18.48	Sqm
(B)	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	38.62	Sqm
(C)	Columns, Pillars, Piers and likes- rectangular or square in shape	24.24	Sqm
7	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	17.98	Cum
8	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS : 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	21.80	Sqm
9	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement : 3 fine sand)	40.06	Sqm
10	Providing and making 12mm thick cement plaster of mix: In Cement mortar 1:5 (1 cement : 5 fine sand)	47.40	Sqm
11	Painting new exterior surface (two or more coats) with PREMIUM TEXTURED paint as per manufacturer's specifications to give -- cleaning washing of surface etc. complete with :On new work (Two or more coats)	87.46	Sqm
12	Add Extra For Electrification work as per Electric SOR 01.06.2020	4000.00	LS


Executive Engineer
Municipal Corporation
Bhilai


Assistant Engineer
Municipal Corporation
Bhilai


Sub Engineer
Municipal Corporation
Bhilai