

MUNICIPAL CORPORATION BHILAI NIT

कार्य का नाम :- वार्ड 31 कर्मा भवन के पास आगंनबाड़ी परिसर अंदर सीमेटीकरण
एवं नाली संधारण कार्य।

(As Per PWD Building & Road SOR works w.e.f 01/01/2015)

SN.	Details of Item	Unit	
1	Demolishing cement concrete including disposal of material within 50 metre lead.1:4:8 or leaner mix	Cum	6.24
2	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	Cum	30.80
3	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc.complete.	Cum	4.40
4	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	Cum	4.40
5	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a)Foundations, footings; base of columns and plinth beam in any shape and size	Sqm	88.00
6	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.1:1.5:3	Cum	7.70
7	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, bindinge as per drawings including cost of binding wire all complete.Thermo-Mechanically treated bars.	Kg	385.00
8	Carriage by mechanical transport for 5 km lead. Earth	Cum	29.63
9	Providing and laying cement concrete for plain concrete/ reinforcedconcrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads)P.C.C. M-25	Cum	10.58

कार्यपालन अभियंता
नगर पालिक निगम, भिलाई

सहायक अभियन्ता
नगर पालिक निगम भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाई