

MUNICIPAL CORPORATION OF BHILAI

NIT

म- वार्ड-69, सेक्टर-9, सी 3 मैदान के समीप प्रकाश व्यवस्था एवं

per pwd building s.o.r. w.e.f. 01/01/2015

	PARTICULARS	QTY	UNIT
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.	13	Cum
2	Surface dressing of the ground including removing vegetation and making up undulations and in-equalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).	76	Sqm
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	3	Cum
3	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	7	Cum
3	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	9	Cum
4	15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	105	Sqm
4	White washing with whitening to give an even shade On new work (Three or more coats).	105	Sqm
5	Distemping with acryli c washable distemper to give an even shade. On new work (Two or more coats)	105	Sqm
5	Providing and placing in position angle iron post and strut of required size including bottom to be split and bent at right angle in opposite direction for required length and drilling holes upto 10 mm dia as per requirement including priming coat with red oxide zinc chromate primer and placing the post/ strut in cement concrete block.	942	Kg
6	Painting on new work (two or more coats) to give an even shade with: Premium synthetic enamel paint	345	Sqm
6	Providing and fixing in position welded steel wire fabric to concrete/ wooden/ angle iron posts including securing and screwing with G.I. tying wire, G.I. staples, G.I.U-nails or steel pins etc., complete	171	Sqm
7	Supply Of Swaged steel tubular Pole as per IS 2713 with base plate of size 300 x 3000 x 6 mm welded at bottom ----- specified height including painting with one coat of red oxide zinc chromate primer. Designation 410 SP-26 height 9.00 metre	5	each
8	Erection of STEEL TUBULAR or "H" BEAM/ ISMB pole in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation and cement concrete collar of size 0.4 metre dia and 0.50 metre height from ground level including excavation and refilling etc. as per specification of length: 7 metre to 10 metre	5	each
9	Supplying and fixing water tight terminal box made of 1.6mm thick M.S. sheet with detachable gland plate in bottom, hinged front open able cover, rubber gasket, having 1 Nos 4way connector and 1 No SPMCB inside the box for cable connection, fixed to pole with 2 Nos clamp made from 40x3mm M.S. flat with 2 No nut bolt dully painted with 2 coat of red oxide paint and 2 coat aluminium paint complete as per specification. 30 x 20 x 15 cms	5	each

	and making end termination with brass compression gland and aluminum lugs following size armoured aluminum conductor power cable of 1.1 KV grade as per specification. 3 X 25 sq. mm (25 mm)	15	each
	supply & fixing & cramping suitable size & all type aluminum ferule/lugs for following size 1.1 KV grade power cable core/lead pressed with high pressure cramping tool including connection to switch gear/MCCB etc as required 25 sq.mm. Item - 17.28.4	10	each
12	Supplying and fixing G.I. pipe along with wall or pole/ support with 2 Nos MS clamps for protection of under ground cable in approved manner including bolts and nuts or metal dash fasteners complete as per specification. 32 mm dia	250	sqm
13	Painting new steel and other metallic surface with red oxide zinc chromide primer paint complete with supply of material labour etc. including preparation of surface	31.5	sqm
14	Supply and fixing following street light pole bracket on existing pole made out of 50 mm dia MS "B" class pipe welded to 300 mm long MS pole canopy of suitable dia at a angle of 102.50 including having MS triangular stiffener of size 150 X 50 X 5 mm thick, making arrangement for tightening the bracket with pole by providing suitable size heavy duty nuts and bolts in canopy, painting with one coat of approved steel primer etc. as per specification. Double Over Hang 1.50 metre Long	10	each
15	Painting wood steel and other metallic surface with Aluminium Paint complete with material and labour including preparation of surface.	31.5	sqm
16	Providing and laying Cast-in-situ cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm including mixing with mechanical mixer, compacting with vibrator, finishing and currying etc. complete but excluding form work.	3.2	cum
17	Providing timber / steel form work for cement concrete work at all levels including removing of the same.	14	sqm
18	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal and salt as per specification and IS Code 3043: 1987(R 2016)	5	set
19	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, multi strand wire in the existing surface/ concealed, FRLS PVC conduit / PVC casing capping as per specification and IS: 694 (2010). 3 x 2.50 sq.mm	90	sqm
20	Providing and fixing porcelain re-wireable fuse carrier and base unit on wooden board including drilling holes on the board, screws, connections etc. as per specification. (Thimbeling shall be paid separately). 32 amps	5	each
	Supplying, installation, testing and commissioning of following 230/250 volts LED street light fitting with all accessories like driver, heat sink made of die cast aluminium with IP 66 protection and 15 KV surge protection on pole bracket, including connection, earthing, Separate housing for driver etc complete as per specification and P.F. should be greater than 0.9. LED chip efficacy ratio ≥ 120 lumens /watt.		
21	90 watt	5	each
	120 watt	5	each
22			
23	Supplying and laying following sizes one number FRLS PVC insulated/XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade direct in ground at a depth not less than 40 cm and upto 90 cm including excavation, sand cushioning, protective covering and refilling the trench etc as per specification, IS: 1554 (1988, Part 1) / IS: 7098 (1988, Part 1). 2 x 16 sq. mm	320	m
24	Supplying, installation, testing and commissioning of following LED Rope light complete as per specification and IP65, P.F. should be greater than 0.75 9 Watt per Metre White / Warm White	75	m

Asstt. Engineer
Municipal Corporation
Bhilai(C.G.)

Sub Engineer
Municipal Corporation
Bhilai(C.G.)

