



# MUNICIPAL CORPORATION OF BHILAI

NIT

कार्य का नाम :- वार्ड-70, निरंकारी साड़ी सेंटर के सामने शहीद चौक हनुमान मंदिर के पास बैडमिंटन कोर्ट निर्माण कार्य

| S.N. | PARTICULARS OF ITEMS  | Quantity | UOM |
|------|---|----------|-----|
| 1    | Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.(In all types of soils.)  | 15.18    | cum |
| 2    | Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.   | 7.59     | Cum |
| 3    | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 1 coarse sand : 4 graded stone aggregate nominal size).  | 15.70    | Cum |
| 4    | Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Pigment Coloured (rubber mould) precast interlock concrete blocks | 75.90    | SQM |
| 5    | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).   | 13.78    | Cum |
| 6    | Carriage by mechanical transport upto 5 km lead:<br>1.26.1 Earth  | 13.66    | Cum |
| 7    | Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)   | 6.90     | SQM |
|      | <b>NON SOR</b>  |          |     |
| 1    | Backed by rich industrial experience and exposure in this domain, devotedly involved in presenting wide assortment of 25mm Artificial Grass.Captivating design Vivacious colors Beautiful pattern.ColorGreen<br>Material PPSHape StraightIs It Washable WashableThickness 25mm(B)   | 81.74    | SQM |

  
Asstt. Engineer  
Municipal Corporation  
Bhilai(C.G.)

  
Sub Engineer  
Municipal Corporation  
Bhilai(C.G.)

