

MUNICIPAL CORPORATION OF BHILAI


NIT


कार्य का नाम- वार्ड-70, एम.आई.जी.-01 / 196 स्थित उद्यान में चेयर एवं प्रकाश व्यवस्था कार्य।

As per Elec sor 2020 & Non sor

SNO	PARTICULARS	QTY	UNIT
1	Supply Of Swaged steel tubular Pole as per IS 2713 with base plate of size 300 x 3000 x 6 mm welded at bottom ----- specified height including painting with one coat of red oxide zinc chromate primer. Designation 410 SP-26 height 9.00 metre	4	each
2	Erection of STEEL TUBULAR or "H" BEAM/ ISMB pole in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation and cement concrete collar of size 0.4 metre dia and 0.50 metre height from ground level including excavation and refilling etc. as per specification of length: 7 metre to 10 metre	4	each
3	Supplying and fixing water tight terminal box made of 1.6mm thick M.S. sheet with detachable gland plate in bottom, hinged front open able cover, rubber gasket, having 1 Nos 4way connector and 1 No SPMCB inside the box for cable connection, fixed to pole with 2 Nos clamp made from 40x3mm M.S. flat with 2 No nut bolt dully painted with 2 coat of red oxide paint and 2 coat aluminium paint complete as per specification. 30 x 20 x 15 cms	4	each
4	Supplying and making end termination with brass compression gland and aluminum lugs for following size armoured aluminum conducto r power cable of 1.1 KV grade as per specification. 3 X 25 sq. mm (25 mm	12	each
5	Supply & fixing & cramping suitable size & all type aluminum ferule/lugs for following size 1.1 KV grade power cable core/lead pressed with high pressure cramping tool including connection to switch gear/MCCB etc as required 25 sq.mm. Item - 17.28.4	8	each
6	Supplying and fixing G.I. pipe along with wall or pole/ support with 2 Nos MS clamps for protection of under ground cable in approved manner including bolts and nuts or metal dash fasteners complete as per specification. 32 mm dia	200	sqm
7	Painting new steel and other metallic surface with red oxide zinc chromide primer paint complete with supply of material labour etc. including preparation of surface	25.2	sqm
8	Supply and fixing following street light pole bracket on existing pole made out of 50 mm dia MS "B" class pipe welded to 300 mm long MS pole canopy of suitable dia at a angle of 102.50 including having MS triangular stiffner of size 150 X 50 X 5 mm thick, making arrangement for tightening the bracket with pole by providing suitable size heavy duty nuts and bolts in canopy, painting with one coat of approved steel primer etc. as per specification. Double Over Hang 1.50 metre Long	8	each
9	Painting wood steel and other metallic surface with Aluminium Paint complete with material and labour including preparation of surface.	25.2	sqm
10	Providing and laying Cast-in-situ cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm including mixing with mechanical mixer, compacting with vibrator, finishing and currying etc. complete but excluding form work.	1	cum
11	Providing timber / steel form work for cement concrete work at all levels including removing of the same.	11.32	sqm
12	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal and salt as per specification and IS Code 3043: 1987(R 2016)	4	set
13	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, multi strand wire in the existing surface/ concealed, FRLS PVC conduit / PVC casing capping as per specification and IS: 694 (2010). 3 x 2.50 sq.mm	72	sqm

14	Providing and fixing porcelain re-wireable fuse carrier and base unit on wooden board (including drilling holes on the board, screws, connections etc. as per specification. (Thimbeling shall be paid separately). 32 amps	4	each
	Supplying, installation, testing and commissioning of following 230/250 volts LED street light fitting with all accessories like driver, heat sink made of die cast aluminium with IP 66 protection and 15 KV surge protection on pole bracket, including connection, earthing, Separate housing for driver etc complete as per specification and P.F. should be greater than 0.9. LED chip efficacy ratio \geq 120 lumens /watt.		
16		90 watt	4 each
17		120 watt	4 each
18	Supplying and laying following sizes one number FRLS PVC insulated/XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade direct in ground at a depth not less than 40 cm and upto 90 cm including excavation, sand cushioning, protective covering and refilling the trench etc as per specification, IS: 1554 (1988, Part 1) / IS: 7098 (1988, Part 1). 2 x 16 sq. mm	188	m
19	Supplying, installation, testing and commissioning of following LED Rope light complete as per specification and IP65, P.F. should be greater than 0.75 9 Watt per Metre White / Warm White	48	m
NON SOR			
1	Providing & Fixing Steel Bench. 3 Seater bench Area - 1.5 m x 0.7 m Height - 0.45 m above Ground level Seating :- made up of 50x25 mm hollow section pipe stand 50x25 mm(thickness) Normal Bore pipe. Painting: - structure have to be powder coated by best quality polyurethane Paints. Benches should be provided with hole passes for proper grip	5	NOS
GST @18%INCLUDED			


 Asstt. Engineer
 Municipal Corporation
 Bhilai(C.G.)


 Sub Engineer
 Municipal Corporatio
 Bhilai(C.G.)