

3 set

**MUNICIPAL CORPPORATION BHILAI**  
**NIT**  
**SUB - मुख्य कार्यालय में कक्ष का संधारण कार्य।**

Sr.no.	Item Discription	No.s	L	B	H	Remark	Unit	Quantity
1	Diluting chemical emulsion (chlorpyrifos/ lindane) in water as per manufacturers recommendation and injecting for pre-constructional curative cum preventive anti-termite treatment:(Five year service guarantee bond to be signed by contractor)							
	Surface treatment by spreading emulsion under floor, over the plinth area before laying base concrete @ 5 litres / sqm	1	10.00	3.00		30		30.00
2	Providing and fixing at all height false ceiling consisting of frame work "W" / "U" / "L" sections made of G.I. sheet with zinc coating of grade 120 consisting of angle cleats of size 25mm wide x 1.6mm thick with flanges of 22mm and 37mm at 1200mm centre to centre one flange fixed to the ceiling with dash fastener 12.5mm diax40mm long with 6mm dia bolts to the angle hangers of 25x25x0.55mm of required length, and other end of angle hanger being fixed with nut and bolts to G.I. channels 45x15x0.9mm running at the rate of 1200mm centre to centre to which the ceiling section 0.5mm thick button wedge of 80mm with tapered flanges of 26mm each having clips of 10.5mm at 450mm centre to centre shall be fixed in a direction perpendicular to G.I. channel with connecting clips made out of 2.64mm diax230mm long G.I. wire at every junction including fixing the gypsum board with ceiling section and perimeter channels 0.55mm thick 27mm high having flanges of 20mm and 30mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450mm centre to centre with 25mm long drive-all screws @ 230mm interval including jointing and fixing to a flush finish of tapered and square edges of the board with recommended filler, jointing tapes, finisher and two coats of primer suitable for board as per manufactures specification and also including						Sqm	35.8664
	Ceilling	1	4.19	8.56		35.8664		
		1	4.6	4.33		19.918		11918
		1	4.6	2.7		12.42		12.42
3	Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.							
	Size 1000x1000	1	4.24	13.87			Sqm	58.79
	Size 1000x1000	1	4.52	4.33		19.5716	Sqm	19.57
	Ceilling							
	Size 1000x1000	1	4.6	2.7		12.42	Sqm	12.42
4	Providing and making plaster of paris moulding bend in approved pattern in ceiling / wall in line and level including scaffolding complete.							
	Above 50 mm and upto 100 mm width and 10mm thick						Meter	89
	Above 50 mm and upto 100 mm width and 10mm thick						Meter	45
	Above 50 mm and upto 100 mm width and 10mm thick						Meter	750
5	Wall painting with acrylic premium emulsion (plastic) paint of required shade to give an even shade.							
	On new work (two or more coats)						Sqm	125
		1	4.5	4.35		68.5125	Sqm	68.5
		1	4.6	2.7		43.47	Sqm	43.47
							Per joint	45.00
6	Applying one coat of cement primer on wall surface (applied @ 0.80 litres/10 sqm) complete						Sqm	125
		1	4.5	4.35		68.5125	Sqm	68.5
		1	4.6	2.7		43.47	Sqm	43.47
7	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.						Sqm	125
		1	4.5	4.35		68.5125	Sqm	68.5
		1	4.6	2.7		43.47	Sqm	43.47
8	Dismantling terrazzo or mosaic or glazed vitreous or patent cement or tiled flooring or dado skirting of any thickness without sub base.							
		1	4.24	13.87			Sqm	58.79
		1	4.52	4.33		19.5716	Sqm	19.57
		1	4.6	2.7		12.42	Sqm	12.42
	ectrical sor							

