


# MUNICIPAL CORPORATION BHILAI (C.G.)


## NIT


कार्य का नाम :- जोन कं. 01 नेहरू नगर में वृक्षारोपण कार्य।

Pwd Building Sor 01.01.2015 & NON Sor Item

S.No.	Description and details of work	Qty.	Unit
1	Supplying and stacking of good earth at site including royalty, loading, unloading and carriage upto 5 km (earth measured in stacks will be reduced by 20% for payment).	200.00	Cum
2	Supplying and stacking at site well decayed cow dung manure from approved source, including loading, unloading and carriage upto 5 km (manure measured in stacks will be reduced by 8% for payment).	200.00	Cum
3	Digging holes in ordinary soil and refilling the same with the excavated earth mixed with manure or sludge in the ratio of 2:1 by volume (2 parts of stacked volume of earth after reduction by 20% : 1 part of stacked volume of manure after reduction by 8%) flooding with water, dressing including removal of rubbish and surplus earth, if any with all leads and lifts (cost of manure, sludge or extra good earth if needed to be paid for separately) : Holes 1.2 m dia and 1.2 m deep.	2000.00	Each
<b>NON SOR ITEM</b>			
1	Providing and Planting of Kadam, Amaltash, gulmohar, shisham, tapidya, Tikoma, Mallshrea, Pletra form, Karanj, Plam, Neem etc.Plant Heighe up to 4 Month Maintenace	2000.00	Each
2	Providing and fixing (Bamboo tree guared)	800.00	Each
3	Providing and fixing UV stabillized Unplasticised Rigid PVC pipes (Single socketed) Having 3.2mm wallthickness 110 mm dia pipe	200.00	Meter

  
**Executive Engineer**  
Municipal Corporation  
Bhilai (C.G)

  
**Asstt. Engineer**  
Municipal Corporation  
Bhilai (C.G)

  
**Sub. Engineer**  
Municipal Corporatio  
Bhilai (C.G)