

MUNICIPAL CORPORATION BHILAI (C.G.)

NIT

कार्य का नाम :- पार्षद निधि से वार्ड-06 संजय नगर सिनेमा कॉलोनी मराठी मोहल्ला के पास बोर खनन कार्य
समबर्सिबल पंप सहित।

Pwd Building Sor 01.01.2015 & Electric Sor 01.06.2020 & Non Sor

S.No.	Description and details of work	Qty.	Unit
1	Carrying out the resistivity survey by VES method using Schlumberger configuration for locating the proper spot for drilling of tube well within the selected habitation, including photography, interpretation of resistivity data and submission of report in the desired format along with resistivity readings, necessary graph and photographs. (only successful point is payable)	1	Point
2	Boring/drilling bore well perfectly vertical for the specified depth suitable to receive required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and submitting strata chart/bore log, including hire & running charges of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer-in-charge upto 90 metre depth below ground level. 125 mm dia.	25.00	Metre
	Rocky strata including Boulders. 125 mm dia.	75.00	Metre
3	Boring/drilling bore well perfectly vertical for the specified depth suitable to receive required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and submitting strata chart/bore log, including hire & running charges of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer-in-charge upto 90 metre depth below ground level. 200 mm dia	40.00	Metre
4	Providing and fixing suitable size threaded mild steel cap or spot welded plate to the top of bore well housing/ casing pipe, removable as per requirement, all complete for bore well of: 150 mm dia	1	Each
5	Supplying, assembling, lowering and fixing in vertical position in bore well, ISI marked G.I. casing pipe (Plain) medium class in 4 to 7 meters length one end fitted with socket as per IS: 1239 (Part-1&Part-2) 1992 with IVth revision (Up-to-date amendments), of reputed & approved make, including required hire & labour charges, fittings & accessories, all complete, for all depths, as per direction of Engineer- in-charge. 125 mm nominal dia	30.00	Metre
6	Supplying, installation, testing and commissioning of submersible pump set for water supply system with submersible motor directly coupled to multi-stage submersible pump of specified discharge capacity, head, delivery size in existing bore well including 2 sets of suitable size holding clamps made out of 50 mm X 6 mm MS flat, connection with suitable submersible cable of standard length etc. as per specification and IS: 694 (2010). Note: submersible Cable should be rust proof, safe from oil / Grease and under water Chemical / abrasion Resistant. 1.5 HP, single phase	1	Each



कार्यालय नगर

विषय -

पार्षद निर्दिष्ट

प. दिनांक

नोट

शाख

शाखा

नस्ती

य नगर सिनेमा

कि नगर पाति

र्ष 2022-23 क

र्य समवर्षिबत


र हुआ है। त


के भवन


2020 दर अनु


कनीकी, वित्त


S.No.	Description and details of work	Qty.	Unit
7	Supply, installation, testing and commissioning of 1-3 HP 1 phase submersible motor starter cum control wall/ floor mounted type made out of not less than 1.6 mm thick MS sheet and comprising of following panel mounting switchgears there in including connection interconnection etc. as required. a) Phase indicating lamps with fuses and toggle switches 1 set b) 1/2/3 HP 1 phase DOL starter with over load and no volt relay 1 No c) 25 A "C" curve DPMCB 1 No d) Voltmeter 0-250 V 1 set	1.00	Each
8	Supplying, laying and fixing following size submersible cable along with GI/PVC/HDFC pipe line or laid in ground etc as per specification and IS: 694 (2010). Note: Cable should be rust proof, safe from oil / Grease and under water Chemical / abrasion Resistant.	100.00	Metre
NON SOR ITEM			
1	Providing ISI Mark 32 mm dia Black H.D.P.E Roll Pipe with Bottom and Top Socket Assembly Fiting all Complete	100.00	Metre
2	3 phase energy meter connection with 4 Core 16mm Service Cable Inculding all installation Charge	1.00	No


Executive Engineer
Municipal Corporation
Bhilai (C.G)


Asstt. Engineer
Municipal Corporation
Bhilai (C.G)


Sub. Engineer
Municipal Corporatio
Bhilai (C.G)


4.7.23


10/7/2023

23/3/23

2/7/23

