



# NAGAR PALIK NIGAM, BHILAI

NIT

वार्ड क्र. 15 अम्बेडकर नगर सड़क जीरो, 5/बी एवं विभिन्न स्थानों में पेवर ब्लॉक संधारण कार्य।

As Per Building S.O.R. 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.		
	In all types of soils.	74.00	cum
2	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8		
		37.00	cum
3	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.		
		37.00	cum
4	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm		
	Pigment Coloured (rubber mould) precast interlock concrete blocks	370.00	sqm
5	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1.5:3		
		8.42	cum
6	Carriage by mechanical transport upto 5 km lead: Earth		
		51.80	cum
			
	ASSTT. ENGINEER		
	Nagar Palik Nigam, Bhilai		
			
	SUB ENGINEER		
	Nagar Palik Nigam, Bhilai		